



Brunswick – Glynn County Joint Water & Sewer Commission

May 4, 2017

PROJECT : Lift Station 4048 Force Main Improvements – Project No. 701

ADDENDUM: Five (5)

DUE DATE: ~~Friday, April 28, 2017 – NOON~~
Wednesday, May 10, 2017 - NOON

THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING CHANGES OR CLARIFICATIONS:

- 1) QUESTION:** In relation to the DI bends and fittings, is the pre-purchased HDPE pipe going to be a comparable O.D so the mega lugs and fittings will bolt straight to the HDPE without HDPE to PVC adapters, and if the fittings bolt straight to the fittings, can an SS Stiffener be used in the HDPE end instead of an adapter?
RESPONSE: The O.D of the pipe will match the fittings, but BGJWSC prefers the MJ adapters instead of stiffeners for HDPE
- 2) QUESTION:** What is the average minimum flow rate for Lift Station 4048?
RESPONSE: The expected pumping rate through the existing 14-inch force main is 3,281 gpm from LS 4005.



All applicants under this Request For Proposal are kindly requested to acknowledge receipt of this Addendum in original only.

**ACKNOWLEDGEMENT
ADDENDUM: FIVE (5)**

Date: _____

The above Addendum is hereby acknowledged:

(NAME OF BIDDER)

Signature

Title