

BID FORM

LIFT STATION 4048 FORCEMAIN IMPROVEMENTS - BGJWSC PROJECT NO. 701

BASE BID (Reference Section 01150 of the Technical Specifications for Scope of Each Item)

Item	Description	QTY	Unit	Unit Price	Total
1	Mobilization, Demobilization, Insurance & Bonds	1	LS	\$	\$
2	Maintenance of Traffic	1	LS	\$	\$
3	Temporary Bypass Pumping	1	LS	\$	\$
4	Temporary 14-Inch Bypass Piping Installed by Open-Cut including Relocation of Existing Utilities, Temporary Fittings, Connection to Existing 14-Inch Force Main and Connection to Existing Manhole	1	LS	\$	\$
5	24-Inch HDPE Installed by HDD (JWSC Pre-purchased Pipe)	1,831	LF	\$	\$
6	24-Inch HDPE Installed by Open-Cut (JWSC Pre-purchased Pipe)	920	LF	\$	\$
7	30-Inch Steel Casing Installed by Jack and Bore	220	LF	\$	\$
8	24-Inch HDPE Installed in Steel Casing with Spacers and End Seals (JWSC Pre-purchased Pipe)	220	LF	\$	\$
9	30-Inch HDPE Installed for Gravity Sewer by Open-Cut and Connections to Proposed and Existing Manholes	1	LS	\$	\$
10	30-Inch DIP Installed by Open-Cut	20	LF	\$	\$
11	14-Inch HDPE Force Main Installed by Open-Cut at LS 4005	20	LF	\$	\$
12	Connect 30-inch DIP for Force Main to Proposed Manhole	1	LS	\$	\$
13	Remove Temporary Bypass Piping and Connect Permanent Piping to Existing 14-Inch CI Force Main	1	LS	\$	\$
14	Connect to Existing 14-Inch CI Force Main at LS4005	1	LS	\$	\$
15	Connect to Existing 18-Inch PVC Force Main Including 18-Inch HDPE Pipe as Necessary	1	LS	\$	\$
16	6-foot Diameter Precast Manhole with Epoxy Coating	1	EA	\$	\$
17	Coat Existing Manhole with Epoxy Coating	14	VF	\$	\$
18	2" Air Release Valve in Manhole	4	EA	\$	\$
19	Remove, Dispose Off-site and Replace Asphaltic Concrete	1,650	SY	\$	\$
20	Remove Unsuitable Material, Dispose Off-site and Replace with Crushed Stone	100	CY	\$	\$
21	Remove Unsuitable Material, Dispose Off-site and Replace with Approved Off-site Fill Material	400	CY	\$	\$
22	Clearing & Grubbing	0.5	AC	\$	\$
23	Grassing, Fertilizing and Mulching	1,000	SY	\$	\$
24	Silt Fence – Sd1-S	250	LF	\$	\$
25	Silt Fence – Sd1-NS	1,700	LF	\$	\$
26	Remove and Replace Signs, Monuments, Mailboxes, Trees/Landscaping, Driveways, Fencing and Other Miscellaneous Items, Including Final Clean-up, Needed for a Complete Job	1	LS	\$	\$
Sub-Total Base Bid		\$			
10% Supplemental Work Allowance		\$			
Total Base Bid		\$			

Total Base Bid in Words: _____