

**FREDERICA ROAD/ATLANTIC DRIVE
SEWER IMPROVEMENTS
BRUNSWICK-GLYNN COUNTY JOINT WATER AND SEWER COMMISSION
RESPONSES DUE DECEMBER 18, 2014
3:00 PM**

**ADDENDUM NO. 1
DECEMBER 15, 2014**

THE REQUEST FOR PROPOSAL IS HEREBY AMENDED AS DESCRIBED ON THE FOLLOWING PAGES. THE PROPOSER MUST ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE SPACE PROVIDED ON THE PROPOSAL FORM. FAILURE TO DO SO MAY RESULT IN REJECTION OF THE RESPONSE.

CLARIFICATIONS

In response to questions received, the following responses/clarifications are offered for the Bidders' consideration:

1. The directional drilling of the 16-inch force main at the intersection of Sea Island Road and Frederica Road has the highest priority. The successful bidder shall plan to complete this portion of the work first. All construction activities associated with this work element shall be planned between midnight and 6:00 A.M.
2. Bidders are reminded to include the E-Verify Affidavit and Agreement with the Bid. Failure to do so will result in the Bid being deemed non-responsive and ineligible for a contract award.
3. The duration of construction for both Phase 1 and Phase 2 (combined) shall be 180 consecutive calendar days.
4. Prior to commencement of construction activities, the successful Bidder shall obtain necessary permits from Glynn County for work on County rights-of-way.
5. In the event of a conflict between the JWSC's Standards for Water and Sewer Design and Construction and the Project Plans and Technical Specifications prepared by Thomas & Hutton, the Project Plans and Technical Specifications shall take precedence.
6. The anticipated peak flow from in the 16-inch force main is 3,500 gallons per minute.
7. The capacity of the 18-inch sanitary sewer on Frederica and Atlantic is not available.

DRAWINGS

Plan Sheet C2.4, Note H – Revise the capacity of each by-pass pump from 1,500 GPM to **3,500 GPM**.

(END OF ADDENDUM NO. 1)