



INVITATION TO BID

**LIFT STATION 2030 Upgrade and Force main Improvements (Part
A) Sea Island Rd Water Main Extension (Part B)**

**BRUNSWICK-GLYNN COUNTY
JOINT WATER AND SEWER COMMISSION**

Office of the Director of Procurement

Issued March 2, 2015

**MANDATORY PRE – BID
CONFERENCE
March 16, 2015 @ 10 a.m.**

Bids Due by 3:00 p.m. •• EST on April 1, 2015

Mr. Drexal D. Paulk, Sr., CPPO, CPPB
Joint Water and Sewer Commission
700 Gloucester Street, Suite 300
Brunswick, Georgia 31520
912-261-7127 or dpaulk@bgjwsc.org
www.bgjwsc.org

Invitation for Bids

Sealed bids for LIFT STATION NO. 2030 UPGRADE AND FORCEMAIN IMPROVEMENTS (PART A) AND SEA ISLAND RD WATER MAIN EXTENSION (PART 8), ST. SIMONS ISLAND, GEORGIA will be received by the Brunswick-Glynn County Joint Water and Sewer Commission (JWSC) at the JWSC's Office of the Director, 700 Gloucester Street, Suite 300, Brunswick, Georgia 31520 until 3:00 p.m. local time, April 1, 2015 at which time and place they will be publically opened and read aloud.

Plans, specifications and bidding documents are on file at the JWSC Main Office, 700 Gloucester Street, Suite 300, Brunswick, GA 31520. Copies may be obtained at the same address by contacting Elizabeth Burns at the JWSC (Phone: 912-261-7126; E-mail: eburns@bgjwsc.org) upon payment of a non-refundable two hundred – twenty five dollars (\$225.00) for each set of documents requested. The documents are also available electronically (CD) free of charge.

The project has a specific sequence of construction which requires the placement and operation of temporary bypass pumping operations at the Lift Station No. 2030 site up front. The sequence of construction also requires the completion of the proposed forcemain prior to the completion of the proposed water main construction.

Part A:

The scope of work for Part A-Lift Station No. 2030 Upgrade and Forcemain Improvements includes approximately 7,400 linear feet of 12-inch PVC forcemain pipe along Rose Cottage Lane and Sea Island Road; 240 linear feet of 14-inch HOPE forcemain pipe along Sea Island Road via horizontal directional drill; 2,400 linear feet of 16-inch PVC forcemain pipe along Sea Island Rd.; 70 linear feet of 16-inch DIP forcemain via (24-inch steel casing) Jack and Bore under Sea Island Rd at Hawkins Island Dr.; 810 linear feet of 18-inch HOPE forcemain pipe via horizontal directional drill under Dunbar Creek; and all labor and equipment to rehabilitate and upgrade an existing lift station (LS2030) into a quadplex lift station, including but not limited to mobilization/demobilization, removal and replacement of unsuitable soils, dewatering, pumps, controls, panels and wiring, temporary bypass pumping, permanent bypass/backup system, all joint materials, fittings, pipe supports, gaskets, adapters, and coatings, flow meter, all testing, soil erosion and sedimentation control, maintenance of traffic, complete surface restoration and all other work and appurtenances shown on the construction plans and specifications or required for the lift station and forcemain system complete and ready for use.

Part 8:

The scope of work for Part 8-Sea Island Rd. Water Main Extension includes approximately 3,000 linear feet of 12-inch PVC water main pipe along Sea Island Road; 80 linear feet of 12-inch DIP water main via (20-inch steel casing) Jack and Bore under Sea Island Rd at Salt Marsh Drive.; 700 linear feet of 14-inch HOPE water main pipe via horizontal directional drill under Dunbar Creek; including but not limited to mobilization/demobilization, removal and replacement of unsuitable soils, dewatering, all joint materials, fittings, hydrants, dewatering, gaskets, adapters, and coatings, all testing and disinfection, soil erosion and sedimentation control, maintenance of traffic, complete surface restoration and all other work and appurtenances shown on the construction plans

and specifications or required for a water main system complete and ready for use.

The Bidder is **encouraged** to examine the location of the work and inform himself fully as to the conditions present at the site. The lift station site is secured ; therefore site visits must be coordinated through the JWSC Planning and Construction Division at (912) 261-7126 , attention Elizabeth Burns, at least 24 hours in advance. A **mandatory pre-bid meeting** will be held in the JWSC main conference room, 700 Gloucester Street, Suite 300 , Brunswick, Georgia 31520 on **March 16, 2015, at 10:00 a.m. local time** followed by a site visit for anyone interested in attending.

A bid guarantee in an amount not less than five percent (5%) of the amount bid must accompany each bid. Acceptable forms of bid guarantees are: a bid bond, certified check or cashier's check made payable to the Brunswick-Glynn County Joint Water and Sewer Commission. Performance and Payment bonds, each in an amount equal to hundred percent (100%) of the contract amount will be required of the successful Bidder.

The Brunswick-Glynn County Joint Water and Sewer Commission provides equal opportunity for all businesses and does not discriminate against any person or business because of race, color, religion, sex, national origin, disability or veteran status. This policy ensures all segments of the business community have access to supplying the goods and services needed by the JWSC.

The JWSC reserves the right to reject any and all bids, waive technicalities and make an award in the best interest of the JWSC.