

Addendum No. 4

Hampton Plantation Water Production Facility

Brunswick Glynn County Joint Water & Sewer Commission

April 29, 2015

ADDENDUM NO. 4

Item No. 1

The following electrical equipment shall be supplied for the Well Soft Starter and High Service Pump VFD's:

Well Soft starter: Danfoss MCD 5-0084B=T7=G1X-00-CV1 for 60 HP unit. Verify control voltage with SCADA vendor before ordering.

High Service Pumps VFD's (2 required): Danfoss Aqua Drive FC202P45KT466_____ for 60 HP unit and shall be provided with analog and digital I/O as required for interface with the SCADA RTU and all other controls. The VFD's I/O configuration shall be coordinated with Data Flow Systems, the SCADA contractor, before ordering.

The VFD does not need a disconnect or braking.

End of Addendum No. 4