



BRUNSWICK-GLYNN COUNTY JOINT WATER & SEWER COMMISSION

August 2, 2019

PROJECT: IFB No. 20-001 – Fiscal Year 2020 Structural Manhole Rehabilitation for the BGJWSC

ADDENDUM: Two (2)

DUE DATE: ~~TUESDAY, August 6, 2019 – 12PM, NOON~~
TUESDAY, AUGUST 13, 2019 – 12PM, NOON

THIS ADDENDUM IS FOR THE PURPOSE OF ANSWERING THE FOLLOWING QUESTIONS:

****THE DUE DATE FOR THIS SOLICITATION HAS BEEN EXTENDED TO TUESDAY, AUGUST 13, 2019 AT 12PM, NOON****

QUESTION 1: Will the Contractor be required to vacuum test those manholes that are on a force main??

ANSWER: Yes. The contractor will be required to plug any lines as necessary to allow vacuum testing of the structure. Proper notification to JWSC will be required 24-48 hours advance planning to coordinate shut down of lift stations. Private lift stations should be able to support temporary plugging to obtain vacuum test. Proper notification of private entities will be coordinated.

QUESTION 2: Will line items be added to the bid form to include removal by material type?

ANSWER: No. Please include in your lump sum pricing for removal of any material that could be found in the manhole.

QUESTION 3: Please explain the process for grit and waste disposal.

ANSWER: Grit only may be disposed of at the BGJWSC location at 139 Indigo Drive, Brunswick GA, 31525. Disposal of Contractor waste including packaging materials and pallets is the responsibility of the Contractor.

QUESTION 4: In the event a new ring/cover is needed, will the replacement be provided by the Contractor or the BGJWSC?

ANSWER: The BGJWSC Operations Division will supply the replacement composite ring and cover, and the installation shall be the responsibility of the Contractor. The Contractor may contact BGJWSC Operations Division to obtain a replacement ring and cover, Kirk Young, 912-717-0428, kyoung@bgjwsc.org

QUESTION 5: Should any steps inside the manhole be removed prior to rehabilitation?

ANSWER: Yes, all existing steps/stairs need to be removed before build up/repair of the manhole.

QUESTION 6: Please list any approved alternatives to Mainstay and Sewpercoat listed in the RFP.

ANSWER: The following coatings have been deemed by BGJWSC staff to be acceptable coatings for this project:

- Mainstay ML-PF by Madewell
- Sewpercoat by Kerneos
- Maximum CA Plus Cement by Standard Cement Materials
- CemTec/HITEC by A.W Cook Cement Products

The following products will NOT be accepted for this project, but BGJWSC staff is interested in learning more about these products and potential one year performance tests:

- OBIC Armor 1000
- OBIC Guard 1306
- Geokrete Geopolymer



All applicants under this Invitation for Bid are kindly requested to acknowledge receipt of this Addendum in original only.

**ACKNOWLEDGEMENT
ADDENDUM: TWO (2)**

DATE: _____

The above Addendum is hereby acknowledged:

(NAME OF BIDDER)

Signature

Title