

PROJECT : BGJWSC Pump Station 2002 Force Main Replacement

**SCHEDULE OF MATERIALS**

LOCATION : St Simons Georgia

ESTIMATOR : Keith Causeway



**SCHEDULE OF MATERIALS**

DATE PREPARED : 7/30/2021	REVISED: 11/02/2021
<b>BASIS FOR ESTIMATE</b>	
(No design completed-Master or Schematic Plan)	
(Preliminary design)	
<input checked="" type="checkbox"/> (Final design)	
(Other)	
Job: 2021-01	

**OPINION OF PROBABLE CONSTRUCTION COST**

Since the Engineer has no control over the cost of labor, materials, equipment, over the Contractor's methods of determining prices, or over competitive bidding or market conditions, the Opinions of Probable Construction Costs provided for herein are made on the basis of his experience and qualifications. These opinions represent his best judgment as a design professional familiar with the construction industry. However, the Engineer cannot and does not guarantee that proposals, bids, or the construction cost will not vary from Opinions of Probable Construction Costs prepared by him.

ITEM	DESCRIPTION	QUANTITY		COST	
		NUMBER OF UNITS	UNIT MEASURE	PER UNIT	TOTAL COST
1	12" DR18 PVC Force Main	1060	LF		
2	12" DR18 FPVC C-900 Force Main	340	LF		
3	12" Dezurik Plug Valve and R.J. Appurtenances	2	EA		
4	12" 22.5° Bend and R.J. Appurtenances (Protecto 401 Lined)	2	EA		
5	12" 45° Bend and R.J. Appurtenances (Protecto 401 Lined)	14	EA		
6	12"x10" Reducer (Protecto 401 Lined)	1	EA		
7	Harness Restraints	50	EA		

**Alternate**

1	12" DIPS DR11 Fusible HDPE Force Main	1060	LF		
---	---------------------------------------	------	----	--	--