



BRUNSWICK-GLYNN COUNTY JOINT WATER & SEWER COMMISSION

June 11, 2024

PROJECT: INVITATION FOR BID NO. 24-011 Construction Services for North Mainland Exit 42 Elevated Storage Tank

ADDENDUM: THREE (3)

DUE DATE: **TUESDAY, JUNE 18, 2024, - 12:00PM, NOON 2:00PM**

**THIS ADDENDUM IS FOR THE PURPOSE OF MAKING THE FOLLOWING
CHANGES AND CLARIFICATIONS:**

- 1) **QUESTION:** The spec calls for an order style Radio RTU: CAT# ESC-4141-GLY. Previous projects have used a cellular RTU: RTU90SEL-2411P. The specification change will impact installation pricing as the antennas are different and mount differently. Will the JWSC provide updated RTU specs or confirm which model is utilized by the utility.

ANSWER: Please utilize the latest RTU 90 design as per JWSC specifications; .

- 2) **QUESTION:** Will the use of Cell Mag antennas be needed on the top or sides of the tank?

ANSWER: Use of Cellular antennas mounted on the modular RTU cabinets are expected unless cell signal inside tank is too poor of quality. Field verify upon installation and testing. (1) 2" Wall penetration for use with the Solar power panel used on all current and future JWSC water tanks will be required. As a minimum, the antenna should be mounted on the tank shaft exterior as the concrete and steel will attenuate the signal.

3) QUESTION: Is there a requirement to have a CL2 analyzer on the water tank?

ANSWER: Yes, this is an EPD requirement.



All applicants under this Invitation for Bid are kindly requested to acknowledge receipt of this Addendum in original only.

**ACKNOWLEDGEMENT
ADDENDUM: THREE (3)**

DATE: _____

The above Addendum is hereby acknowledged:

(NAME OF BIDDER)

Signature

Title